



VERDE DESIGN

2455 The Alameda,  
Santa Clara, CA 95050  
408.985.7200p | 408.985.7260f  
www.verdedesigninc.com

ADDENDUM

ADDENDUM NO.: 3  
 DATE: MAY 31, 2022  
 BID DATE: JUNE 2, 2022  
 BID TIME: 2:00 PM  
 PROJECT NAME: BASEBALL INFIELD & SOFTBALL OUTFIELD IMPROVEMENTS AT LIBERTY,  
 FREEDOM & HERITAGE HIGH SCHOOLS

VERDE'S PROJECT NO.: 211110  
 OWNER'S PROJECT NO.:  
 CONSTRUCTION MANAGER: PAUL MELLONI  
 FILE NAME AND PATH: Y:\Projects-SC\2021\2111100 - Liberty HS BB Imp\Bidding\Addendum 3\LUHSD - Addendum 3.docx

NOTICE TO ALL CONTRACTORS SUBMITTING BIDS FOR THIS WORK AND TO ALL PLAN HOLDERS:

You are hereby notified of the following changes, clarifications or modifications to the original Contract Documents, Project Manual, Drawings, Specifications and subsequent Addenda. This Addendum shall supersede the original Contract Documents, and previous Addenda wherein it contradicts the same and shall take precedence over anything to the contrary therein. All other conditions remain unchanged.

CONFORMANCE WITH CONTRACT DOCUMENTS, PROJECT MANUAL DRAWINGS AND SPECIFICATIONS

All addenda work shall be in strict conformance with the Contract Documents, Project Manual, Drawings and Specifications as they pertain to work of a similar nature.

**ITEM NO. 1:**

Contractor RFIs

RFI Question:	Response:
Insurance Documents and Endorsements: 1. This section references OCIP documents. Please provide the OCIP insurance requirements so it can be fully reviewed.	District to review
General Conditions: 2. Article 11 Insurance and Bonds indicates insurance to be provided by the Contractor. Please clarify conflict with the requirement for OCIP.	District to review
All School Sites Sheet L3.2: Demolition Plan Softball: 3. Existing fines legend states to remove 4" of infield fines and reuse as base material and refer to Detail F Sheet D2.1. Detail F only shows a 2" section of infield fines. Please clarify if the replaced section should be a total depth of 4" consisting of 2" existing infield fines and 2" on new imported infield fines.	2" of reused existing infield fines as the base with 2" of new imported infield fines on the surface.
All School Sites Sheet L7.2: Material and Details Refence Plan Softball Field:	Per addendum 1, Revised Material and Detail References Plans and Construction Details Sheet D2.1 were issued.

Contractors

<p>4. Heritage and Liberty plans reference a Detail M / D2.1 for a concrete band at existing fence. This detail is not shown on any of the school site plans. Please provide a detail that shows the condition where the synthetic field meets existing fence line showing a curb in front of the fence line and post footings.</p>	<p>12" Wide Synthetic Turf Edgeband at Existing Fence shown as Detail M, Sheet D2.1.</p>
<p>5. Freedom L7.2 does not show a callout for a curb at fence line. There is #13 for 6" band at natural turf H/D2.1, which is not shown on the plans. This detail does not show the condition at an existing fence line.</p>	<p>At Freedom softball field, the existing fence has an existing edgeband. Concrete Sub-curb (callout 1) to be installed at existing fence edgeband. Refer to Addendum 1 for revised Material and Detail Reference Plans.</p>
<p>6. All Sites Callout #1 is indicated for the perimeter, but the detail is for where existing concrete is adjacent to the synthetic turf, which not the case at many of the site conditions. Please clarify all required bands and details that show the adjacent conditions.</p>	<p>Refer to Addendum 1 for revised Material and Detail References Plans.</p>
<p>All Sites Sheet D2.1: Construction Details:          7. Detail G indicates clay bricks just 1/2" below the surface. The material plans show this hatching at all the pitchers mounds. Detail B / D3.1 states entire mound shall be built out of clay. Please clarify the required material to build all the pitchers mounds.</p>	<p>At baseball pitcher's mounds, entire mound to be built out of bagged clay per specs.</p>
<p>All Sites Sheet D3.1 and Heritage Sheet D3.2 Athletic Details:          8. Detail B Pitchers Mound – Baseball does not show any depth below the finish grade surface. Please show and clarify the depth of fines required below the finish grade since the clay should not taper to zero depth at the edges.</p>	<p>Depth shall be 6" to the concrete / synthetic turf edge.</p>

By: Derek McKee  
 Verde Design

Addendum No. 3 is hereby acknowledged by the bidder's signature.

\_\_\_\_\_  
 Name of Bidder's Company

\_\_\_\_\_  
 Authorized Signature

\_\_\_\_\_  
 Date

\_\_\_\_\_  
 Title

END OF ADDENDUM